

**VACUUM
EXCAVATION**

VACTOR[®]

HXX HYDR

excavator



***A safe, cost-effective alternative
for underground construction
and municipal use***

Introduction

Every day, contractors, municipalities and utilities excavate for installation of underground facilities, or must locate existing pipes, cables and lines for maintenance and repairs. In the past, this usually involved digging by hand (often a slow and tedious process) or with a mechanical excavator, backhoe or similar machine.

Every year, there are numerous reports of injuries, deaths, explosions and fires from unsafe or poorly planned excavations that strike underground facilities or result from collapsed trenches. Many of these incidents can be avoided and the risks minimized by utilizing techniques such as vacuum excavation.

Definitions

Vacuum excavation is a general term that may include processes using either water (hydro-excavation) or high-pressure air to loosen soil. In either case, an air vacuum is used to move the loose soil and rocks, often into a debris tank for later disposal or back-filling the hole that's been made.

Hydro-excavation is a process that utilizes pressurized water to break up and remove the soil via air

conveyance (vacuum) into a debris tank, providing a non-destructive means to safely locate utilities and precisely excavate an area.

This white paper will focus specifically on hydro-excavation and its origins, benefits, safety factors, applications and economic value.

Historical perspective

Hydro-excavation as we know it today can trace its growing popularity to the Canadian oil and gas industry, which realized years ago the efficiency of using a hydro-excavation machine to "daylight" buried gas pipes and other utility lines. With cold weather and permafrost, petrochemical plants and facilities in Canada found that using heated water made hydro-excavation the only viable option to excavate year-round.

In the early 1960s, catch basin cleaners were adapted for hydro-excavation use, but the technology was crude. Vactor® built its first hydro-excavation machine, the "ExcaVactor," in 1969. However, the market then was immature and it was the only unit built.

In the 1970s and '80s, customers modified vacuum trucks and sewer cleaners for hydro-excavation use. Some took vacuum components off the trucks and mounted them on all-terrain vehicles to get into remote locations. In the 1990s, a number of companies saw a growing demand for hydro-excavation machines and began manufacturing truck- and trailer-mounted units in varying configurations.

By 2000, hydro-excavation was widely used across Canada and was moving into the United States. In recent years, the practice has rapidly gained acceptance in the U.S. and is now widely used by utility contractors for locating and non-destructive digging.

Safety and damage prevention

Improved safety and damage prevention top the list of key benefits of hydro-excavation. An underground utility strike can be catastrophic, affecting thousands of people and costing millions of dollars. A single incident may cause personal injury or death, property damage, lost work opportunity, community disruption, ecological damage and insurance liability.

More than 40 percent of pipeline system leaks and ruptures are caused by damage from outside force, and more than half of all cable service outages are caused by excavation damage.

While disruption of a telecommunications network is not as inherently dangerous, it can be expensive and inconvenient, impacting traffic control systems, health services and emergency response activities. The importance of minimizing underground utility strikes and their consequences cannot be denied.

Using hydro-excavation in such situations can avoid:

- “Hits” or “strikes” on underground utility lines, cables and pipes
- High costs to repair damaged infrastructure
- Costs and inconvenience of interrupted utility services
- Serious injury or death to workers and the public
- Liability and increased insurance costs
- Loss of a company’s reputation, revenues and employee morale

In addition, hydro-excavation can improve overall productivity and efficiency for contractors, municipalities and utilities.

Government regulation

The U.S. presently has more than 14 million miles of buried utilities and pipes. Current laws prohibit the use of mechanical means to dig within 18 inches of buried cable and pipe in the U.S., and 45 cm in Canada. Buried utilities are often mis-marked or maps are inaccurate, requiring underground facilities to be located by sight, either by hand-digging or another means, to maximize safety. This is often called “daylighting.” Unfortunately, digging by hand is often time-consuming, and mechanical excavation is inherently risky.

The U.S. Department of Transportation’s Damage Prevention Quality Action Team views the situation this way:

The United States has a vast underground infrastructure of pipelines, conduits, wires, and cables that affect every individual. This underground infrastructure is critical to our way of life, constantly providing oil and natural gas, telecommunications, electricity, water, sewage, cable TV, and other vital products and services. Disruption of any of these underground facilities could affect the safety of the public, the environment, and continued service reliability that could impact our entire economy.

One of the leading causes of disruption to our country’s underground facilities is external force damage (sometimes called ‘third-party damage’) that occurs during excavation activities. This has been recognized by both industry and government. Although such damage occurs far too frequently, it is usually preventable. Responsibility for preventing excavation damage is shared by all stakeholders. Advanced planning, effective use of one-call systems, accurate locating and marking underground facilities, and the use of safe-digging practices can all be very effective in reducing underground facility damage. In most states, increased and mandatory use of the state’s one-call system has significantly reduced the incidence of excavation damage. However, damage still occurs.

Risky business

Strikes on natural gas lines are particularly hazardous and occur all too often, resulting in significant property damage, injuries and even deaths. The tables below illustrate incidents for natural gas distribution pipelines during the years 2005-2009.

Natural Gas Pipeline Operators Incident Summary Statistics By Year 2005 – 2009

Distribution Operators

Year	No. of Incidents	Fatalities	Injuries	Property Damage
2005	170	12	39	\$499,342,741
2006	142	18	30	\$23,885,966
2007	153	9	36	\$25,635,544
2008	150	6	56	\$57,377,214
2009	158	10	50	\$31,901,300
Totals *	2,672	291	1,191	\$935,663,469

* Totals include accidents from 1990 - 2009. Source: Office of Pipeline Safety Statistics.

As these statistics show, the cost of property damage for natural gas pipeline operators can vary dramatically depending on the nature and severity of the incident. Of the 158 incidents reported in 2009, 43 were caused by excavation damage, resulting in more than \$5.03 million in property damages and 1 fatality.

Distribution Pipeline Incident Summary By Cause 1/1/2009 - 12/31/2009

Cause	No. of Incidents	% of Total Incidents	Property Damages	% of Total Damages	Fatalities	Injuries
Car, truck or other vehicle not related to excavation activity	20	12.6	\$3,316,350	10.4	4	14
Fire/explosion as primary cause	35	22.1	\$6,354,164	19.9	0	2
Operator excavation damage	3	1.9	\$200,356	0.6	0	0
Third-party excavation damage	40	25.3	\$4,835,241	15.1	1	7
Totals	158	100.0	\$31,901,300	100.0	10	50
Average			\$316,255			

Totals and averages include all accidents from 2009. Source: Office of Pipeline Safety Statistics. Data for 2010 not available at time of publication.

Applications

Virtually every construction contractor, municipality and utility does underground construction and/or has subsurface facilities. At times, a subcontractor with expertise or specialized equipment is needed to handle certain excavation jobs. There are many potential applications in which hydro-excavation is a viable option. These include:

- Line location, installation and repair for utilities and pipelines Backhoe, Dump truck
- Sewer and pipe rehabilitation Restoration (196 sq. ft.) 1.5 hrs.
- Telecommunications maintenance and repair
- Slot trenching
- Waterline maintenance and repair
- Directional drilling
- Sign and pole installation
- Landscaping (i.e., digging holes for new trees and shrubs)
- Repair work or excavation in tight spaces and congested areas
- Potholing

With hydro-excavation, buried natural gas and petroleum pipelines can be uncovered without risk of puncture. Fiber optic cables, telephone lines, water mains and other utilities can be efficiently located without damage. This method also causes less surface damage, traffic disruption and other potential digging drawbacks. Operators can use hydro-excavators to dig with precision, offering a less invasive method for slot trenching, potholing or pipe location. In grassy areas, sod can be replaced and, within a week, a casual observer would never know a hole had been dug there.

Cost/benefit analysis

To effectively evaluate the costs versus benefits of hydro-excavation compared to mechanical excavation methods, worksheets such as the ones on the next page can be used. The first worksheet in each of the two sets includes typical figures for the example shown. Use the second, blank worksheets to plug in your own numbers and compare conventional digging and hydro-excavation.

In most cases, a yard-for-yard comparison between a hydro-excavator and a bucket machine favors the bucket machine. However, the actual removing of the dirt is only a small part of the overall job.

Let's look at the following job as an example: Acme Utility Co. has contracted you to uncover a 2 ft. x 2 ft. area they believe to be six feet underground, then backfill with clean material and restore to its original condition.



Option 1



Option 2

Option 1: Conventional method

Open hole with sloped sides to allow for legal hand digging for exposure of utility.

Operation	Time	Cubic Yards	No. in Crew	Amount
Unchain, unload & stage equipment	0.5 hr.			
Uncover utility	3 hrs.	13.3	4	
Backhoe, Dump truck				
Backfill (compacted)	2 hrs.	12.1		
Restoration (196 sq. ft.)	1.5 hrs.			
Reload equipment	0.5 hrs.			
Totals	7.5 hrs.	25.4		

Operation	Time	Cubic Yards	No. in Crew	Amount
Unchain, unload & stage equipment				
Uncover utility				
Backhoe, Dump truck				
Backfill (compacted)				
Restoration (196 sq. ft.)				
Reload equipment				
Totals				

Option 2: Hydro-excavation method

Open hole for exposure of utility. There's no need to slope the sides, because this process keeps workers on the surface, not in the excavation.

Operation	Time	Cubic Yards	No. in Crew	Amount
Park truck, turn on vacuum & water	5 min.			
Uncover utility	0.5 hr.	0.9	2	
Hydro-excavator				
Backfill (compacted)	25 min.	0.9		
Restoration (sod was cut & peeled back at start of excavating)	1.5 hrs.	1.2		
Totals	2.5 hrs.	3		

Operation	Time	Cubic Yards	No. in Crew	Amount
Park truck, turn on vacuum & water				
Uncover utility			2	
Hydro-excavator				
Backfill (compacted)				
Restoration (sod was cut & peeled back at start of excavating)				
Totals				

These tables illustrate the time, labor and cost savings between the different methods. The Option 1 crew will likely be occupied onsite almost all day, while Option 2's crew has time for multiple jobs in one day. This may or may not be a typical example in your area.

Cost/benefit analysis worksheets used with permission of www.safeshovel.com.

Today's technology

The most effective hydro-excavators today are dedicated units designed and built specifically for hydro-excavation. They combine high-pressure water systems that cut through and break up sod and soil with a high-flow air vacuum that lifts soil and small rocks out of the excavation area.

In the late 1990s, Vactor® Manufacturing saw that customers needed a dedicated machine, resulting in the Vactor HXX Hydro-Excavator introduced in 1999.

Fan or PD

On most dedicated hydro-excavators available today, customers may choose either a fan system or a positive displacement (PD) blower as the vacuum source. Each has distinct advantages:

- A fan system moves an incredible amount of air, excavating more rapidly than other systems. It's also easier to operate and maintain, and the unit's overall weight is usually less. Also, fan units are generally less expensive than the PD versions.
- A PD blower moves air over longer distances and generates higher amounts of vacuum, allowing for excavation at greater depths, but at slower speeds, than fan units.

Vactor® Manufacturing understands that users often have unique applications that lead to a preference for one type of vacuum system, so both positive displacement blower and fan machines are available.

In either the fan or PD configuration, a simplified airflow path design will maximize pickup and filtration effectiveness. Additional features that improve the unit's overall productivity include extendable or telescopic booms offering a wide range of rotation and mounted on the curb side, large-capacity water tanks and debris bodies, heavy-duty solid construction, heated pump and hose reel cabinets, convenient operator controls and tool storage.

Advantages of Hydro Excavating

- Acts as its own lubricant
- Controls static electricity
- Avoids the sandblasting effect of air
- Works in almost all soil conditions
- Can be heated to excavate frozen ground

Advantages of Air Excavation

- No need to refill water tanks
- Drier material for backfilling
- Very efficient for loose soil
- Faster clean-up time
- Compressor available for air tools

Vactor recommends in most cases using three to nine gallons per minute (gpm) of water volume for hydro-excavation. Contractors are paid to excavate the soil, not to dump debris, recover water or get more water. Therefore, using the proper water volume is cost-effective and saves time. In addition, the resulting debris has minimal water content, not a slurry as with systems using high water volumes, which often allows debris to be put back into the excavation.

Vactor recommends using water pressures between 1,500 and 2,000 psi. Pressure higher than 2,500 psi is unsafe. Operating a hydro-excavator at the proper water pressure virtually eliminates the chance of damaging line covers or casings, as well as operator injury.

Industry outlook

Many facilities and areas in Canada have experienced intolerance to utility strikes and, as a result, they now rely heavily on hydro-excavation. The U.S. still has somewhat of a tolerance for hits as a "cost of doing business," although that's changing.

Enhanced enforcement from a government level may drive contractors increasingly toward vacuum and hydro-excavation in coming years. While legislation has been enacted in a few cities and states across the U.S., those examples are limited. However, many people in the industry say it's just a matter of time.

The vacuum excavation market will have to deal with plenty of unknowns in the near future - a recovery of directional drilling, the possibility of a fiber resurgence, and further legislation to prevent "hits" and enforce existing one-call regulations.

Conclusion

At the time of this publication, it looks like hydro-excavation will continue to grow in acceptance and popularity for the foreseeable future. Contractors are increasingly finding value in hydro-excavation for themselves and their customers. More municipalities are gaining confidence in the practice as new projects are completed.

Hydro-excavation can significantly reduce the unknown or unintended consequences from any project involving drilling, trenching or excavation. Whatever the future holds, hydro-excavation is here to stay and gaining ground.

We trust that this information was educational and valuable.

VACTOR[®]
Subsidiary of Federal Signal Corporation

For more details, contact:
Vactor Manufacturing, Inc. 1621 S. Illinois St.
Streator, IL 61364
Phone: 815-672-3171
Toll-free: 800-627-3171 Fax: 815-672-2779
E-mail: sales@vactor.com
www.vactor.com